


Construction and Parameters

Construction Series	- FS T0 Tracker
Connection	- 15 String
GCR	- 0.4
System Rotation	- no
Number of Structures (4 x 15)	- 3757
Number of Modules	- 225420
Type of Modules / Power	- FS4120-3 / 120W-DC
Inverter	- 9 x SunGrow SG3000HV

Sketch from the Table Section

Sketch Construction Series

Plant System Rating - 27.050400 MWp-DC



LEGEND

---	SITE BOUNDARY
PP	POWER POLE
X	CHAIN LINK FENCE
O	BARBED WIRE FENCE
OP	EXISTING POWER LINE
---	SITE SETBACKS
---	TEMPORARY LAYDOWN AREA
---	SWITCHGEAR AND CONTROL EQUIPMENT
---	SITE ACCESS ROAD
---	SOLAR TRACKER
---	INVERTER AND TRANSFORMER STATIONS

DISCLAIMER: THIS DRAWING AND DESIGN IS COPYRIGHT PROTECTED WHICH SHALL NOT BE USED, REPRODUCED OR REVISED WITHOUT WRITTEN PERMISSION BY WSP CANADA INC. THE CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS AND UTILITY LOCATIONS AND REPORT ALL ERRORS AND OMISSIONS PRIOR TO COMMENCING WORK. THIS DRAWING IS NOT TO BE SCALED.

ISS/REV	DATE	DESCRIPTION	DES	CHK	PM
6	2017-12-08	ISSUED FOR AUC	MA	--	--
5	2017-11-06	RE-ISSUED FOR FINAL	MA	--	--
4	2017-11-03	RE-ISSUED FOR FINAL	MA	--	--
3	2017-10-31	ISSUED FOR FINAL	MA	--	--
2	2017-10-18	RE-ISSUED FOR APPROVAL	MA	GW	TP
1	2017-08-29	ISSUED FOR APPROVAL	MA	TP	TP
0	2017-05-31	ISSUED FOR REVIEW	MK	TP	TP

CLIENT: **solarkrafte**

CLIENT REF NO:

PROJECT: **CASSILS SOLAR PROJECT**

PROJECT NO: 171-01873-00

ORIGINAL SCALE: AS SHOWN

DATE: 2017-12-08

DESIGNED BY: MA

DRAWN BY: MA

DISCIPLINE:

TITLE: **WEST BROOKS SITE PLAN**

DRAWING NO: **C-001**

SHEET NO: OF

ISSUE: **ISSUED FOR AUC**

DATE: 2017-12-08

ISS/REV: **6**

